

09 June 2025

Dear Bidders,

CLARIFICATION NOTICE

**BID: CONSTRUCTION OF PALISADE FENCING AT RUNDU CAMPUS:
W/RFQ/UNAM-08/2025.**

Please be informed of the following amendment: the total fencing distance has been revised from 451m to **650m**. This change has been updated in **Section III: Statement of Requirements and Section IV: Price Schedule** of the bid document, attached as Annexure A on the following page, or alternatively, you can also download the updated RFQ bid document. Bidders are advised to take note of this revision and adjust their submissions accordingly.

For queries:

- **Technical Queries**, if any, should be addressed to **Mr. Barnabas Nangombe**, Rundu Estate Officer at T: 061-2686000 Email: bnangombe@unam.na

PROCUREMENT MANAGEMENT UNIT

SECTION III: STATEMENT OF REQUIREMENTS

SCOPE OF WORKS, SPECIFICATIONS AND PERFORMANCE REQUIREMENTS

The scope of work includes:

Manufacture, Supply and Installation of Palisade Fencing at Rundu Campus. The distance to be covered by the fence is **650m**. The height of the panels should be **1.8m high** and in **3m long**, made out of steel **2mm thick or better**.

A sample photo of the palisade fence is shown below:



The proposed materials to be used are as per the Priced Activity Schedule and the table below, **However, the bidder is advised to attend the compulsory site meeting on 20 June 2025, 10h00. at Rundu Campus.** and ascertain the exact requirements.

DESCRIPTION
Excavation work
Building work
Welding work
Painting work

SECTION IV: PRICED ACTIVITY SCHEDULE

Procurement Reference Number: **W/RFQ/UNAM-08/2025**

Complete the unit and total prices for each item listed below. Authorise the prices quoted in the signature block below. The quantities shown below are approximate and not subject to re-measurement for payment purposes.

Item No	Brief Description of Works	Quantity	Unit of Measure	Unit Price (N\$)	Total Price (N\$)
A*	B*	C*	D*	E	F
<i>Site Establishment</i>					
1	Contractors P & G	1	Sum		
<i>Construction and Welding work</i>					
2	Foundation for Intermediate SHS Columns, 300x300x700mm	1	Sum		
3	Construct Concrete footing with a strength 20MPa after 28 days	650	m		
4	Ensure Column centre to centre, 3000m	1	Sum		
5	Horizontal Angle Iron to be fitted 300mm above dwarf wall	1	Sum		
6	Horizontal Angle Iron to be fitted 300mm lower than top	1	Sum		
7	Ensure Space between vertical irons, 90mm	1	Sum		
8	Vertical irons to be welded 50mm above dwarf wall	1	Sum		
9	Ensure Concrete dwarf wall to be 150 wide x 400 deep between columns	650	m		
10	Construct Concrete footing strength 20MPa after 28 days	650	m		

11	Construct Dwarf wall, 50mm of mesh encased in concrete	650	m		
	Paint & Others				
1	All steel work to be painted factory primed on undercoat	1	Sum		
2	Two coats of high gloss enamel paint, colour Terracotta- brown	1	Sum		
3	Removal of existing diamond mesh fence	650	m		
4	Site cleaning / clearing of area	1	Sum		
				Subtotal	
Enter 0% VAT rate if VAT exempt. Bidders not registered for VAT must not include VAT.				VAT @ %	
				Total	

Name:		Signature:	
Position:		Date:	
Authorised for and on behalf of:	Company		